BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer, Dasarahalli Division
SCHEDULE - B

NAME OF THE WORK: Construction & Development of 12th Cross Park in Ward No 14 Bagalagunte

Sl. No	Description of work	Unit	Qty	Rate to be Quoted by Contractor Sri N.C.Ravi Kumar	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Construction of sub-grade and earthen shoulders with approved material Gravel/Murrum with all lifts & leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table No. 300-2 complete as per specifications, including cost of earth, watering charges & compaction by vibratory roller to 97% of modified proctors density) complete as per specifications and directions of engineer in charge of the work	Cum	1920	382.0	Rupees Three Hundred Eighty Two Only
2	Extra for laying earth by mechanical means as per specifications for compaction in 250mm thick loose layers when laying of earth in layers is done from stacked materials including breaking of clods and dressing but excluding rolling and watering including cost of all labour, HOM complete as per specifications and directions of engineer in charge of the work	Cum	1920	64.0	Rupees Sixty Four Only
3	Extra for watering the earth to bring the earth upto required optimum moisture content manually including cost of all labour complete as per specifications and directions of engineer in charge of the work	Cum	1920	13.0	Rupees Thirteen Only
4	Construction of footpath/separator by providing a 150 mm compacted granular sub-base as per Clause 401 & 25mm thick cement concrete grade M-15, overlaid with precast concrete tiles in cement mortar 1:3 including provision of all drainage arrangements but excluding kerb channel complete as per specifications and directions of engineer in charge of the work	Sqm	586	750.0	Rupees Seven Hundred Fifty Only

Signature of the Contractor

Executive Engineer
Dasarahalli Division
BBMP

EXECUTIVE ENGINEER
Bruhat Bengaluru Mahanagara Palike
Dasarahalli Division, Bengaluru-73.

Scanned with CamScanner